8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work	Unit	Dispensary	Midwife's quarters	New kitchen to inpatients, wards	Total
Earthwork excavation and filling in basement ...	C. yd.	97	22	6	125
Size stone in chunam for foundation and basement ...	C. ft.	3,371	...	...	3,371
Burnt stone in chunam do do ...	,,	...	790	261	1,051
Brick in chunam (superstructure)	,,	5,541	1,209	386	7,136
Burnt stone slabs, dressed	S. ft.	868	168	29	1,065
Cut stone pillers, complete	No.	13	10	...	23
Chunam plastering	Sqr.	81·78	27·28	7·15	116·21
White and color-washing	,,	81·78	25·64	7·15	114·57
Teakwood work with oiling	C. ft.	161	39·29	13·20	213·49
Roofing with first class Mangalore tiles with teak reepers, complete	Sqr.	29·73	7·36	2·40	39·49
Ridge tiles set in mortar	R. ft.	92	26	15	133
Teakwood eave board, ornamental, complete... ...	,,	400	48	...	448
Teakwood finials	No.	18	...	...	18
Teakwood pannelled doors	S. ft.	228	...	...	228
Teakwood windows top 2 feet glazed only and the rest pannelled outside and glazed inside with iron bars, etc., complete	,,	32	...	...	32
Teakwood windows inside glazed outside pannelled with iron bars	,,	220	...	...	220
Ventilators, glazed, with iron bars	,,	128	...	..	128
Chacolate painting	Sqr.	15·01	3·9	·64	18·74
Tarring	L. S.	L. S.	L. S.	L. S.	L. S.
Clearing site and levelling ground	,,	,,	,,	...	,,
Cement pointing	Sqr.	34·68	...	...	34·68
Flooring with Kadapa slabs on 3" concrete bed and cement pointing	,,	6·65	2·32	·60	9·57
Flooring with Mangalore square tiles on 3" concrete bed and cement pointing	,,	11·88	1·60	...	13·48
Completing sham windows	L. S.	L. S.	...	...	L. S.
Iron-hold fasts to doors and windows	No.	152	46	...	198
Chunam plaster mounds to verandah roof all along valleys and ends of verandah	L. S.	L. S.	...	...	L. S.
Chunam plaster mouldings over ventilators on front gable with cornice inscription letters, etc. ...	,,	,,	...	...	,,
Teakwood ceiling, ½" thick, complete	Sqr.	12·32	2·05	...	14·37
Cup boards and wall shelves	L. S.	L. S.	L. S.	...	L. S.
Brick in chunam coping and plastering	R. ft.	...	49	...	49
Teakwood battened doors, complete	S. ft.	...	103	18	121
Do windows with iron bars, complete... ...	,,	...	41	14	55
Expanded metal ventilators	,,	...	21	...	21
V-shaped and lead off drains	L. S.	...	L. S.	..	L. S.
Binding wall of brick in chunam	R. ft.	...	45	...	45
Constructing a masonry chimney to kitchen	L. S.	...	L. S.	L. S.	L. S.
Pestle and mortar to kitchen	,,	...	,,	...	,,
Constructing seats in latrine, stone flagging, cement pointing, tarring, 3' feet high and drainage pipe ...	,,	...	,,	...	,,
Ventilating tiles	No.	...	...	4	4

V. AIYASWAMI IYER,
Executive Engineer.

SHIMOGA DIVISION.

Notice dated 17th December 1910.

A sum of Rs. 12-13-4, being balance of security deposit amount of F. Lobo, late Sub-Overseer of this Division, is outstanding in deposits in this office. If the said amount is not claimed within three months after this date either by him or his heirs, the same will be credited to Government

F. A. STEELE,
Executive Engineer.